

FICTIONAL DEMONSTRATION - NOT FOR CONSTRUCTION USE

Risk assessment and method statement

Document ID	SHQ-DEMO-RAMS-003	Status	Revision 3 - working example
-------------	-------------------	--------	------------------------------

A project-specific RAMS example showing scope, sequence, controls and a readable risk-rating presentation for competent review.

Risk-rating key

Low	1-4	1-4	Proceed with stated controls
Medium	5-9	5-9	Supervisor review and monitoring
High	10-16	10-16	Do not proceed until reduced
Very high	17-25	17-25	Stop; redesign the task

Task and people

Activity	Soft strip of Level 4 office partitions and suspended ceilings
People at risk	Operatives, other trades, visitors and building occupants
Supervisor	Sam Taylor (fictional)
Competence	Training and task competence to be checked before work

Method sequence

1	Confirm work area, service information and asbestos information
2	Establish exclusion, access and waste routes
3	Complete required isolations and verify status
4	Remove in controlled sections and segregate waste
5	Inspect area, record progress and hand over

Hazards and controls

Live services	Approved isolation process; competent verification; stop if information conflicts
Falling material	Controlled sequence, exclusion zone and suitable access equipment
Dust and debris	Task controls, extraction/suppression and suitable RPE where assessment requires it
Manual handling	Plan loads, team lift or use handling aids

Review before issue

Unknowns	Physical service locations and final access arrangements require site verification
Decision	Competent person must amend, approve and issue the real project version

Fictional demonstration. SiteHQ prepares and controls the record; a competent person reviews the real project and approves the work.